

# CSDM 2019 - PRELUDE

## System Engineering to deliver first FLNG

Alain POINCHEVAL


Technip France – President

Paris December 12<sup>th</sup>, 2019




# The Concept : a first of a kind

## Build an Offshore version of an Onshore LNG facility !




4 FIFA Soccer  
fields, 105mx65m  
Prelude FLNG



# Shell Prelude FLNG

## How to manage complexity through system engineering

- The largest floating facility ever built
- Gas treatment for liquefaction /Storage / off loading
  - Length: 488 m. - Width: 74 m.(USS enterprise 351m)
  - Weight:
    - Steel: 260,000 tons
    - Displacement: ~600,000 tons
    - Topsides 82000 tons
    - Cooling water : 50 000 m3/h sea water = 3mn to fill an Olympic swimming pool
- 200km from nearest land/design to resist to class 5 cyclone
- Up to 25 years on station
- Up to 250m water depth
- Safety: Goal Zero –(55mmh- 12 LTI– 4mmh off shore 1 LTI)
- Annual Production
  - 3.6 Mtpa LNG capacity/1.3 Mtpa condensate/0.4 Mtpa LPG




### Turret Mooring System:


- 4 Production Risers
- Mooring Lines (4 x 4)
- Turret: 93 m height/ 12000 t

### Topsides Modules:

- 14 modules
- Separation, Dehydration, Liquefaction, Boilers
- Associated utilities



# A multi-center execution plan to manage risk & complexity



# ...due to multiple challenges...

## Mechanical

- Offloading LNG between two vessels on the high seas
- Importing large quantities of high pressure feed gas on a floating facility
- Equipment and piping loads generated by motion (towing & in-place conditions)
- LNG tank sloshing over 25 years without dry docking
- Industrial Maturity vs. FLNG specifications

## Process

- Gas processing facilities adapted to marine environment
- Compact design (weight and volume)
- Designing for motion compared to static onshore plant

## Engineering

- Specific new challenges for Compliance to Australian regulation and Offshore safety design.

# System Engineering

## A Data Centric approach and breakdown structure management

### ❖ Data Centric achieved through a unique master 3 D modelling operated from multi location

- PDMS 3D architecture- digital Twin
- Single integrated commissioning system for marine and production/storage/offloading systems rationnel

### ❖ Design breakdown / work breakdown/construction breakdown /system breakdown /cost Breakdown

- To follow phases down to final delivery necessity to break systems
- Design phase
- Engineering phase
- Construction phase
- Commissioning phase
- Start up & operation phase
- Marine system
- Loading system
- Mooring system
- Process sytems
- Utility system
- Storage systems
- .....




# Lessons Learned & Success Factor


- Vision & value to goal zero sharing with customer
- Consortium mgt
- Pre com & com maximised before sail away .
- Novelty mgt into an EPC LS project
- Stress & fatigue excellence (piping & structural design)

- « Flawless Project Delivery program » implemented from design to start up.
- constructability of modularization (liftability, congestion, module density).
- Develop new design processes with multiple interdependences (blast, motion acceleration etc.)
- Customer intimacy build
- Sponsor ship
- Progressive conversion to derisk .

# TECHNIPFMC & SYSTEM ENGINEERING



- TechnipFMC is deploying System Engineering
- in an agile way
  - in collaboration with other actors from the O&G supply chain
  - using digital transformation to accelerate implementation






# TECHNIPFMC IS ACTIVE IN THE INCOSE O&G WORKGROUP

Hosted at TECHNIPFMC premises

Organized with TechnipFMC, SHELL, Equinor and BP. One and half days of workshop on Digital Management of Requirements

40+ participant from the industry: Operators, OEMs, EPCs, Standard Bodies



Oil & Gas  
Working Group



